

# QC Metallurgical, Inc.

## Testing & Consulting Services

2870 Stirling Road • Hollywood, FL 33020-1199 • (954) 889-0089 • Fax (954) 362-5742

### INSPECTION REPORT Addendum Report 07/15/2021

DATE July 1, 2021

QCM JOB# 21EM-315 CUSTOMER AnchorLift Direct

DESCRIPTION 1 sample 964420 Anchor Connector Swivel 16-20 MM/5/8"-3/4"

Chain, Anchors

CUSTOMER ORDER# 1241 MATERIAL Solid AISI 316L Stainless Steel

INSPECTION SPECIFIED Proof Load Testing

APPLICABLE SPECIFICATIONS \_\_\_\_\_

### RESULTS OF INSPECTION

#### TEST RESULTS PROOF LOAD


Swivel Connector:

Large End: 1.580" W x 2.6" D x 0.862" Diameter Pin

Small End: 0.909" W x 2.0" D x 0.700" Diameter Pin

Initial Load (lbs.): 52,800 lbs. Held for 2 minutes; no damage.

Ultimate Failure Load (lbs.): 67,400 lbs. Failure of load frame attachment.  
Shackle began deformation.

  
Jerry Iacofano